



**BIDS AND AWARDS COMMITTEE (BAC)**

**SUPPLEMENTAL BID BULLETIN NO. 2022 – 019**

November 25, 2022

This Supplemental Bid Bulletin No. 2022 – 019 for the project: Infrastructure and SMART Campus Development Operationalization of Face-to-Face Classes and Upgrading/Procurement of Equipment (Existing General Education Building) is issued to amend the following Sections in the Bidding Documents:

**I. Changes in the Section VI. Performance Specifications and Parameters**

FROM	AMENDMENTS/CHANGES
<p><u>(FOR ITEM NO. 2)</u></p> <p>12. DOORS</p> <p><b><u>For Smart Faculty Hub to Conference Room</u></b></p> <p>Use kiln-dried panel door with viewing glass.</p> <p>Use G.I. pre-fab door jambs.</p> <p><b><u>For Main Doors (8 Classrooms)</u></b></p> <p>Use tempered frameless glass door with ½” thick glass with complete accessories like door locks, door hinges, door handles &amp; closers. (Please see attached Drawings)</p>	<p><u>(FOR ITEM NO. 2)</u></p> <p>12. DOORS</p> <p><b><u>For Smart Faculty Hub to Conference Room and Electrical Room</u></b></p> <p>Use kiln-dried panel door with viewing glass.</p> <p>Use G.I. pre-fab door jambs.</p> <p><b><u>For Main Doors (8 Classrooms)</u></b></p> <p>Use tempered frameless glass door with ½” thick glass with complete accessories like door locks, door hinges, door handles &amp; closers. (Please see attached Drawings)</p>

### 13. ELECTRICAL WORKS

#### III. Power System

- Building's Electrical Service Entrance connection shall have underground roughing-in provisions (electrical manholes) for the underground cabling distribution from the Electrical Three-phase Power house situated nearest to the building structure.
- Use 400-Volts line to line, 230 volts line to neutral service 3-phase, 4-wire entrance connection for the building.
- Entrance wires shall be in rigid steel conduit embedded and protected sufficiently underground.
- A grounding system shall be installed that is compliant to the provisions of the Philippine Electrical Code.
- Building's Electrical distribution system shall have Normal power and Emergency power distribution.
- Electrical room shall be provided with complete signage.
- Old panelboards shall be removed and old electrical connections of the building shall be integrated to the new electrical system.
- Future loads shall be included in the electrical computation of the building.
- Building's Main Distribution Panel shall have LED Digital Panel Multi-Function Meter for at least Current and Voltage functions.
- Distribution Panels shall be installed for each floor of the building.
- All Smart Hub and Faculty Hub Rooms shall have its own Electrical Panel
- All Panel boards shall be power-coated, ground-bonded and with lockable doors.
- All Panel boards and all Branch circuits shall be properly labelled and tagged.
- The system shall be ready for emergency power (alternate source) connection in case of brownout.

### 13. ELECTRICAL WORKS

#### III. Power System

- Building's Electrical Service Entrance connection shall have underground roughing-in provisions (electrical manholes) for the underground cabling distribution from the Electrical Three-phase Power house situated nearest to the building structure.
- Use 400-Volts line to line, 230 volts line to neutral service 3-phase, 4-wire entrance connection for the building.
- Entrance wires shall be in rigid steel conduit embedded and protected sufficiently underground.
- A grounding system shall be installed that is compliant to the provisions of the Philippine Electrical Code.
- Building's Electrical distribution system shall have Normal power and Emergency power distribution.
- Electrical room shall be provided with complete signage.
- Old panelboards shall be removed and old electrical connections of the building shall be integrated to the new electrical system.
- Future loads shall be included in the electrical computation of the building.
- Building's Main Distribution Panel shall have LED Digital Panel Multi-Function Meter for at least Current and Voltage functions.
- Distribution Panels shall be installed for each floor of the building.
- All Smart Hub and Faculty Hub Rooms shall have its own Electrical Panel
- All Panel boards shall be power-coated, ground-bonded and with lockable doors.
- All Panel boards and all Branch circuits shall be properly labelled and tagged.
- The system shall be ready for emergency power (alternate source) connection in case of brownout.



<ul style="list-style-type: none"> <li>• Power outlets shall be adequate for office functions.</li> <li>• Smart Hub and Faculty Hub Computers shall have its own electrical circuit and outlets.</li> <li>• Install floor outlets if space and room utilization so require (discourage the use of extension wires for power connection).</li> </ul>	<ul style="list-style-type: none"> <li>• Power outlets shall be adequate for office functions.</li> <li>• <b>Electrical connections with Nema 3R and appropriate circuit breakers for Airconditioning Unit shall be provided.</b></li> <li>• Smart Hub and Faculty Hub Computers shall have its own electrical circuit and outlets.</li> <li>• Install floor outlets if space and room utilization so require (discourage the use of extension wires for power connection).</li> </ul>
---	--

**II. Changes in the Section VII – Drawings**


**III. Changes on the name of the project in the Section VIII – Bill of Quantities**

<b>FROM</b>	<b>AMENDMENTS/CHANGES</b>
NAME OF PROJECT:  <b>DESIGN AND BUILD FOR THE</b> INFRASTRUCTURE AND SMART CAMPUS DEVELOPMENT OPERATIONALIZATION OF FACE-TO-FACE CLASSES AND UPGRADING/PROCUREMENT OF EQUIPMENT	NAME OF PROJECT:  INFRASTRUCTURE AND SMART CAMPUS DEVELOPMENT OPERATIONALIZATION OF FACE-TO-FACE CLASSES AND UPGRADING/PROCUREMENT OF EQUIPMENT

The foregoing shall form as an integral part of the Bidding Documents. Any Provision in the Bidding Documents inconsistent herewith is hereby amended, modified & superseded accordingly.

For the information & guidance of all concerned.

Sincerely,

  
**EDUARDO F. AQUINO, MS**  
 Chairperson, Bids and Awards Committee